



0	1	2	3	4	5 = 3 x 4
6	RCSR08A%	Zugraveli lavabile, vopsea-acetat de polivinil-vinacet, la int/ext, 2str, pe tencuiii exist.	mp	480.00	manopera: utilaj: transport:
greutate materiale		tone	0.75		
manopera		ore	292.80		
6.L	6103232	Vopsea alba v.101-2 ntr	kg	216.00	
7	RPCJ41A-01%	Strat de amorsaj pt.tencuiii int.si ext.executat cu mortar uscat de ciment aplicat manual - pentru armarea cu plasa fibre sticla	mp	131.00	manopera: utilaj: transport:
greutate materiale		tone	1.61		
manopera		ore	98.25		
8	RPCR08B%	Vopsirea,zugraveli lavabile,vopsea pa baza de aracet-vinacet,la int-ext,2 straturi,glet ipsos exist. tavan	mp	131.00	manopera: utilaj: transport:
greutate materiale		tone	0.18		
manopera		ore	49.78		
8.L	6104353	Vopsea vinarom alba v.108-210 stas	kg	39.30	
9	RPFC13A%	Revizuirea instalatiilor electrice la cladiri, instalatiile fiind executate cu...conductor din cupru	ml	652.00	manopera: utilaj: transport:
greutate materiale		tone	0.01		
manopera		ore	58.68		
10	RPCO09	Demontarea timplariei din lemn (usi,ferestre,obloane,glasvanduri)inclusiv sortarea si stivuirea lor	mp	32.40	manopera: utilaj: transport:
greutate materiale		tone	0.23		
manopera		ore	21.60		
11.L	2938940	Fereastră rasin simp ext 2c cerc lcrim sft-1,50mp	mp	17.28	
12	CK33A+	Usi din PVC, cu un singur canat, montate cu diburi din plastic, etansarea rosturilor cu spuma poliuretamica si cordon de silicon, având suprafata tocului...pană la 2,5 mp inclusiv;	mp	15.12	manopera: material: utilaj: transport:
greutate materiale		tone	0.39		
manopera		ore	12.85		
12.L	6313356	Diblu cu expandare marimea 10	duc	105.84	
12.L	20012686	SILICON PENTRU STICLA		3.78	



STADIUL FIZIC: Bloc Locuinte		Pag 3	
0	1	2	3
12.L	20012728	SPUMA POLIURETANICA PENTRU PISTOLI	4.54
12.L	6720309	Usa din profile PVC - tip hewl	15.12
14	CMJ30B02B1	Conducte de alimentare cu apa rece, din tevi pvc, tip g si m. Montat coloana din teava pvc tip g diam, ext, concl. = 32—40 mm	240.00
15	ACE08A1	Umplutura in..sant. la cond. de alim. cu apa si canalizare cu: nisip	20.00
16	RPCXA03A	Umplutura...de pamant	100.00
19	TSC03B1	Sapatura mecanica cu excavatorul de 0.40-0.70 mc,cu motor cu ardere interna si comanda hidraulica, in ..pamant cu umiditate naturala,descarcare in depozit teren catig 2	0.20
20	ACD01H1	Capac si rama stas 2308-81 pentru camine...cu piesa suport necarosabil tip ii	1.00
21	ni78452*	Montare bazin vidanjabl	1.00
21.L	2452959	Bazin vidanjabl, racord dn 125, gura de vizitare dn 600 cu capac, V=10 mc	1.00
22	ACE08A1	Umplutura in..sant. la cond. de alim. cu apa si canalizare cu: nisip	2.50
23	RCSA06A%	Umplutura de pamant, exec.in str.orz. mana, incl.imprastiatul	31.00
gretate materiale			
gretate materiale		tone	3.46
manopera		ore	1.53
gretate materiale			
gretate materiale		tone	0.03
manopera		ore	12.00
gretate materiale			
gretate materiale		tone	0.66
manopera		ore	2.20
gretate materiale			
gretate materiale		tone	10.00
manopera		ore	215.00
gretate materiale			
gretate materiale		tone	27.68
manopera		ore	12.20
gretate materiale			
gretate materiale		tone	3.10
manopera		ore	34.72



Executant,

Director General

Raport generat cu ISDP, www.devize.ro, e-mail: suport@intelsoftdeviz.ro, tel.: 0236 477.007

1 euro = lei, curs la data de

Cheltuieli directe:		Recapitulatie 1 octombrie 2014		CAS		Fond de risc		Concedii si indemnizatii		Somaj		Fond de garantare		Sanatare		Total Inclusiv Cheltuieli Directe:		Cheltuieli indirecte		Total Inclusiv Cheltuieli Indirecte:		Profit		Total Inclusiv Profit:		TOTAL GENERAL (fara TVA):		TVA:		TOTAL GENERAL:	
manopera	procent	material	manopera	utilaj	transport	total																									
0	1	2	3	4	5 = 3 x 4																										
30	RPSF04C*	Evacuarea apei din subsol cu..electropompa portabila	mc	10.00																											
31	RIZN14110asimREPARATII GARD BETON H=1.60 m	ml	38.00																												
		manopera	4.35																												
		ore																													
		manopera	3,344.00																												
		ore																													