

- lei -		06.10.2017		SECTIUNEA TEHNICA		SECTIUNEA FINANCIARA	
F3 - LISTA cuprinzand cantitatile de lucrari							
- lei -							
06.10.2017							
Pag 1							
OBIECTIV:	Reparatii Comuna Creaca						
OBIECTUL:	Reparatii Camin Jac						
Beneficiar:	Comuna Creaca						
Proiectant:	S.C. Hatchback EXE						
Executant:							
nr.: _____							
nr.: _____							
Project: _____							
Plansa: _____							
Faza: _____							
Nr. Capitolul de lucrari		U.M. Cantitatea					
0		1		2		3	
1		4		5 = 3 x 4			
<b>1 Reparatii Sala Camin</b>							
1.1 RCSJ03A%		Reparatii tencuieli int.brute, pereti zidarie		mp		225.00	
gretate materiale		tone		28.86			
manopera		ore		216.00			
Tavanutul planseelor din lemn : reparatii la		mp		125.40			
gretate materiale		tone		2.05			
manopera		ore		97.81			
1.3 RCSR08B%		Zugravelli lavabile, vopsea-acetat de		mp		365.25	
gretate materiale		tone		0.52			
manopera		ore		193.58			
1.3.L 6103232		Vopsea alba		kg		109.58	
90-80							
<b>2 Reparatii BIROU</b>							
2.1 RCSJ03A%		Reparatii tencuieli int.brute, pereti zidarie		mp		44.00	
gretate materiale		tone		5.64			
manopera		ore		42.24			
2.2 RPCH17C%		Tavanutul planseelor din lemn : reparatii la		mp		44.00	
gretate materiale		tone		0.72			
manopera		ore		34.32			
2.3 RCSR08B%		Zugravelli lavabile, vopsea-acetat de		mp		44.00	
gretate materiale		tone		0.06			
manopera		ore		34.32			

STADIUL FIZIC: Lucrari de Reparatii

0	1	2	3	4	5 = 3 x 4
manopera	ore	23.32			
2.3.L 6103232	Vopsea alba	v.1012 ntr	kg	13.20	
	90-80				

3 Reparatii Acoperis/Sarpanta

3.1 RPCH06A%	Reparatii la elem.de sarpanta deteriorate:prin platuri(crapaturi-rupturi la albaletrieri,diagonala)	buc	15.00		
		material:			
		manopera:			
		utilaj:			
		transport:			
greutate materiale	tone	0.13			
manopera	ore	11.70			
3.2 RCS008E%	Revizuire sipcilor , inlocuirea lor	ml	12.00		
		material:			
		manopera:			
		utilaj:			
		transport:			
greutate materiale	tone	0.15			
manopera	ore	9.72			

3.3 CE03C# Inlocuire tigle ceramice asimilat

		material:			
		manopera:			
		utilaj:			
		transport:			
greutate materiale	tone	0.09			
manopera	ore	15.75			
3.3.L 2300045	Tigla solzi din ceramica	buc	35.25		

Cheltuieli directe: Recapitulatie 1 octombrie 2014

CAS					
Fond de risc					
Concedii si indemnizatii					
Somaj					
Fond de garantare					
Sanatate					
Total Inclusiv Cheltuieli Directe:					
Cheltuieli indirecte					
Total Inclusiv Cheltuieli indirecte:					
Profit					
Total Inclusiv Profit:					
TOTAL GENERAL (fara TVA):					
TVA:					
TOTAL GENERAL:					

1 euro = lei, curs la data de

Executant  
 Director General